

BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64

No. EE/YNK/BBMP/E-PMT/21/2017-18 Dated: 06-03-2018

APPROVED TENDER SCHEDULE - 'B'

Item No: 02

Name of Work:-Construction of CC roads at Narayanappa Layout in ward No 04

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Chenna Krishna P	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift up to 1.5m,excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no142, PWD SR 2016-17)	Cum	315.90	90.92	Rupees Ninety and Paise Ninety Two Only
2	KSRB 100-1 Loading and unloading of stone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumping turning for return trip excluding time for haulage and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 cost of haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4)	Cum	315.90	103.78	Rupees One Hundred Three and Paise Seventy Eight Only
3	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P 12/L 4.3)/ PWD SR 2016-17	Cum	58.95	5396.33	Rupees Five Thousand Three Hundred Ninety Six and Paise Thirty Three Only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Chenna Krishna P	
				Rate	Rate in Words
4	Providing and laying Plain /reinforced cement concrete for side drains wall and bottom thickness 15cm using M20 nominal mix concrete with OPC cement at 300kg with 20mm and down size granite metal coarse aggregate at 0.69 cum and fine aggregate at 0.43 cum machine mixed well compacted for walls at bottom including centring shuttering cost of materials HOM of machineries curing etc.completeexcluding cost of steel as per MORTH specification No.1500,1700,2200 Page No 265 lte mo 37.59.2 SR 2016-17	Cum	5.40	11539.97	Rupees Eleven Thousand Five Hundred Thirty Nine and Paise Ninety Seven Only
5	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46/ PWD SR 2016-17	Qntl.	4.32	6742.03	Rupees Six Thousand Seven Hundred Forty Two and Paise Three Only
6	Providing precast slab of 250 mm thick including cost of all materials, labour, curing,transportation,loading ,unloading,etc.,complete as per the direction of engineer in charge-	Sqm	9.00	5346.11	Rupees Five Thousand Three Hundred Forty Six and Paise Eleven Only
7	RCC Precast covering slab for drain (10cm thick)	Sqm	40.50	2196.60	Rupees Two Thousand One Hundred Ninety Six and Paise Sixty Only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Chenna Krishna P	
				Rate	Rate in Words
8	KSRRB M600-6: cement concrete pavement, construction unreinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause 1051.2.2M20/M30 at 380/450 kg per cum, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25mm, mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including leveling the form work as per drawing,), spreading the concrete with shovels, rakers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved curing compound, finishing to lines and grade as per drawing complete as per specification M30(at 360kg per cum coarse aggregate	Cum	72.00	6503.99	Rupees Six Thousand Five Hundred Three and Paise Ninety Nine Only
9	Vaccum De- writing with vacuum pump and suction mat and compaction with skin flater clubbed with floatiog disc including cost of generator, HOM of machinery Sereed Vibratory Power Floaterblade and diisc etc. with all lead and lift. Page No 177 Item No 22.7 SR 2016-17	Sqm	480.00	99.79	Rupees Ninety Nine and Paise Seventy Nine Only
10	Providing groove cutting for width of 5mm to 100m depth 80mm-100 including cost of cutting machine, generatoe & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot birumen fillars, and filler metal etc., including cost of conveyance of all materials,. Labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. do- for concrete pavement Item no 22.8.1 Page No 178 SR 2016-17	Rmt	150.00	127.51	Rupees One Hundred Twenty Seven and Paise Fifty One Only

P. Chenna Krishna
Signature of the Contractor

Vaunt
Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.